KOLAR DIVISION.

Notice dated 2nd November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of the 24th November 1928, for Restoration of Manchenahalli Hosakere, Major Tank, Bagepalli Taluk, An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M. except on holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees three hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the Restoration of Manchenahalli Hosakere, Bagepalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenders must quote rates for each item of work both in figures and words.

10. The tenders stating that the work would be executed a certain percentage in excess or lower than the sanctioned estimate will not be accepted.

Detailed Abstract Estimate for Restoring Manchenahalli Hosakere Major Tank in Bagepalli Taluk.

Items of work	Per	Quantity
Bund at R. L. 56·50.		
(1) Earthwork to bund including all lead and lift, with watering and consolidation.	C.yd.	4,287
(2) Turfing to bund including all lead and lift, with watering and consolidation.	S.yd.	4,779
(3) Removing and resetting old stone revetment with new jelly ..	C.yd.	622
(4) New stone revetment with new jelly	,,	658
(5) Fixing new grade stones with numbering and painting, etc., complete.	Each	21
(6) Index stones with numbering and painting, etc., complete	,,	21
(7) Register No. stone Survey and constructive details ...	,,	1
(8) B. M. stones, complete	,,	2
(9) Gauge stone, compelte	,,	1
(10) Clearing prickly pears and lantana bushes	Grade	15
Breach filling.		
Clearing sand and loose soil in the bed	C.yd.	1,605
Cutting grips on both sides	L. S.	Rupees
Excavating foundation	C.yd.	23
Gravel backing	,,	116
Constructing puddle wall with good clay with watering and tamping.	,,	236
Earthwork to Bund	,,	1,745
Total to Bund ...	..	...